

BRUHAT BANGLORE MAHANAGARA PALIKE



DASARAHALLI-ZONE

T.DASARAHALLI-SUB-DIVISION.

Name of Work: Improvements to drain & Footpath
11th cross Right Side Bhuvaneshwari Nagara In
Bagalagunte ward No 14

Estimate Cost :- 5.00 Lakhs

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work :- Improvements to drain & Footpath 11th cross Right Side Bhuvaneshwari Nagara In Bagalagunte ward No 14

			Est. Cost Rs.				5.00	Lakhs	
Sl. No	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.152/I.19.2 PW, P & IWTD - SR 2013-14)	Cum							
	Cross		1	150.50	0.80	0.50	60.20		
							60.20	90.72	5461.00
	Basic Rate	84.00							
	Add Area Weightage 8%	6.72							
	Total	90.72							
2	Removing B.S.Slab of drain and stacking etc., complete Page No. 28/ Item No. 5.32/ PWD SR 2013-14	Sqm							
	Cross		1	150.50	0.90		135.45		
			Consider 60% Qty				81.27		
							81.27	50.11	4073.00
	Basic Rate	46.40							
	Add Area Weightage 8%	3.71							
	Total	50.11							
3	KSRRB 4-1.3: Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3) PWD - SR 2013-14)	Cum							
	Cross		1	150.50	0.45	0.15	10.16		
			2	150.50	0.20	0.15	9.03		
							19.19	4211.38	80811.00
	Basic Rate	3973.00							
	Add Area Weightage 6%	238.38							
	Total	4211.38							

[Signature]

4	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6) PW, P & IWTD - SR 2013-14)	Cum							
			1	150.50	0.45	0.08	5.08		
	Approach Slab		2	150.50	0.20	0.10	6.02		
							11.10	4690.50	52062.00
	Basic Rate	4425.00							
	Add Area Weightage 6%	265.50							
	Total	4690.50							
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 28/ Item No.5.33/ PWD SR 2013-14	Sqm							
			Qty Vide Item No 2				81.27		
							81.27	70.04	5692.00
	Cross								
	Basic Rate	64.85							
	Add Area Weightage 8%	5.19							
	Total	70.04							
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick (P. 27 I. 5.31.1) Page No. 28/ Item No. 5.31/ PWD SR 2013-14	Sqm							
			1	150.50	-	0.90	135.45		
			Deduct Availabe Qty Vide Item No 2				81.27		
	Basic Rate	318.00					54.18	343.44	18608.00
	Area Weightage 8%	25.44							
	Total	343.44							
7	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 27/ Item No. 5.27/ PWD SR 2013-14	Sqm							
			2	150.50	0.40		120.40		
	Cross						120.40	924.48	111307.00
	Basic Rate	856.00							
	Add Area Weightage 8%	68.48							
	Total	924.48							
8	Supplying and fixing precast reinforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm							
			1	150.50	0.90		135.45	1600.00	216720.00
	Data Rates Approved by CE DZ								

Sumit

[illegible]

CERTIFICATE

Assistant Engineer
Ward No.14

A/S

TC(DH) AS 264/13-14, 30/10/13


05.00 label (Rupee
Five label only)

Page No. 237

SL. No. 264

ced m h 2016

Name of work: Improvement to drain & Foot path
 11th cross Right side Bhuvaneshwari nagar
 in Bagalagunta. ward No. 14



Location of work spot

[Signature]

[Signature]

Sanitization Officer
 District Health Officer
 District Health Officer
 District Health Officer